



Information Management for Automated Demand Response in Large Facilities

Mary Ann Piette

Lawrence Berkeley National Laboratory

Demand Response Research Center

Demand Response R&D Symposium

November 30, 2004

drirc.lbl.gov/autodr2





Project Overview

Goal: Evaluate feasibility of Automated DR hardware & software systems in large facilities

- ♦ Can control & communications systems receive signals & execute automated shedding?
- ♦ Control strategies for max load sheds & min service loss?

R&D Team: LBNL, Infotility, Shockman Consulting

15-Minute Price





2003 Automated-DR Sites



Albertsons – East 9th St. Oakland

Engagenet

Bank of America – Concord Technology Center

Webgen

General Services Admin - Oakland Fed. Building

BACnet Reader

Roche Palo Alto – Office and Cafeteria

Tridium

Univ. of Calif. Santa Barbara – Library

Itron Silicon Energy







Auto-DR System Communications



1. LBNL defines price schedule
2. Price published on XML server
3. Clients request price from server every minute & send shed commands
4. EMCS carries out shed





Methods: 2003 and 2004 Tests

Field Tests

- ◆ Recruit, define strategies & measurement (detailed electricity, temperature, and trend-log analysis)
- ◆ 2003: 5 buildings, 1.5 million ft²
- ◆ 2004: 18 sites, 40 buildings, 10 million ft²


Connectivity

- ◆ Internet Gateway - Internet to EMCS
- ◆ Internet Protocol Relay (IP Relay) – Internet controlled relay (2004 only)






Results: 2nd Test November 2003





Results: Retest Sept. 2004 Oakland Federal (90°F)





DR Shed Strategies

	HVAC											Lighting, misc.			
	Zone temperature increase	Supply air temp reset	Fan VFD limit	Fan off	Duct static pressure reset	Cooling valve close	Cooling fan-coil off	Direct chiller limit	Chilled water temp reset	Boiler pump (reheat) off	Electric humidifier off	Common area lighting	Office lighting shed	Anti-sweat heater shed	Transfer pump off
Albertsons												✓		✓	
B of A		✓	✓		✓										
GSA Oakland	✓														
Roche				✓											
UCSB Library			✓		✓	✓									
450 GG	✓														
NARA	✓														
Echelon	✓											✓	✓		
Monterey												✓			
300 CapMall	✓		✓	✓					✓						✓
50 Douglas	✓														
Summit Ctr	✓														
Cal EPA					✓							✓	✓		
Kadent															✓
USPS SJ								✓							
CISCO	✓						✓			✓		✓	✓		
CETC				✓							✓				
OSI Soft	✓														



Results: 1st 2004 Scaled Up Test


	IP Relay	Succeeded	Server Problem	Other Problem	Not Ready
Albertsons		x			
B of A	x	x			
GSA Oakland			x		
Roche		x			
UCSB				Gateway down	
450 GG			x		
NARA			x		
Echelon		x			
Monterey		x			
OSIsoft					x
300 Capitol	x	x		Maintenance	
50 Douglas	x	x			
Summit Ctr	x	x			
Cal EPA	x				x
Kadant				Maintenance	
USPS		x			
CISCO		x		EMCS	
CETC					x
Total	5	10	3	4	3




Results: 2004 Office Buildings




300 Capitol Mall: Whole Building Power and Baseline




50 Douglas: Whole Building Power and Baseline



300 Capitol Mall: Mechanical Power and Baseline



Summit Center: Whole Building Power and Baseline





Summary and Next Steps



- ★ **Automated DR is technically feasible**
- ★ **New knowledge needed to develop, operate & evaluate technology & strategies for DR**
 - ◆ Rebound/recovery strategies needed
 - ◆ Link to daily efficiency clear to operators
- ★ **Future R&D**
 - ◆ Guides to DR shed strategies
 - ◆ Scalable automation, security, latency, XML standards
 - ◆ Pilot tests with utilities, peer to peer forums
 - ◆ Economic evaluation tools/real-time simulation/scenario analysis